

KGN FIRE PROTECTION PRODUCT TRADING



382 Sta. Natividad St. Brgy. San Isidro Paranaque City

VAT Reg. TIN: 366-378-880-00000

Cellphone Number: (Mr. John)09692772298 | (Mr. Christopher) 09616486145

Email address: kgnmanagement888@gmail.com

Facebook: KGN Extinguisher

TO: **GLACIER PARANAQUE REFRIGIRATION SERVICES CORP.**

SUBJECT: Preventive Maintenance of Fire Detection Alarm System (FDAS)

Please find price quotation below for your guidance and reference. Please feel free to contact us for clarification

Scope of Work

The Service Provider shall be responsible for the performance of the services as follows:

Fire Detection Alarm System Control Panel

- c Check all switches of Control Panel
- c Check of all modules and terminals
- c Check of all terminal lags and wirings for field devices
- c Check and clean terminal log of all back up batteries
- c Check of all terminal logs and wirings for field devices
- c Check and inspect for any unusual appearance or condition, and make necessary correction as required.
- c Manual testing of control panel.
- c Troubleshoot and repair if necessary

Smoke Detectors

- c Check all the smoke detectors installed.
- c Check terminal log of smoke detector base, if corroded - clean immediately
- c Random activation of all smoke detector without discharge of agent

Manual Pull Station

- c Check terminal log of all manual release station.
- c Clean lever of button for normal operation and repair if necessary
- c Inspect all manual release station for broken, crack, dirt, distortion and or any signs of physical damage.
- Mo-c Testing of all manual release station without discharge of agent.

Fire Alarm Bell

- c Check all the audible signal of fire alarm bells.
- c Cleaning of all fire alarm bells.
- c Inspect all fire alarm bells for any signs of physical damage.
- c Testing of all fire alarm bells using back up battery operation..

Horn & Flashing Strobe

- c Check all the audible signal of horns & flashing strobes.
- c Cleaning of horns & flashing strobes.
- c Inspect horn & flashing strobe for any signs of physical damage.
- c Activation of all hornstrobe using back up battery operation.
- c Testing of all fire alarm bells using back up battery operation.

Backup Battery

- c Clean and check of back up batteries.
- c Check proper voltage supply and proper termination.

Actual Testing

- c Testing of Control Panel using cross zone system without discharge of agent.
- c Testing of DC power supply using of back up batteries with an operation of 30 minutes.
- c Cleaning of all smoke detector head.
- c Actual testing of all field devices such as manual station, fire alarm bell, abort station, horn and flashing strobe.
- c Actual testing of smoke detector using smoke tester..

Note: Replacement Parts, if necessary, are the responsibility of the client and will be charged separately


NOTE: Sign & Sealed Fire Safety Maintenance Report and Sign & Sealed Certificate will be Provided.

TERMS OF PAYMENT

50% - Down payment.

50% - upon completion

Total Service Cost: 165,000

Sincerely,

John Richard M. Navarro
Owner